


JINGZHANG RISING Overall Spatial Structure and Land-Use Planning

BOARD 01 / 03 · Spine, terraces, wings and stitches | three scope tiers | land use
Strategic scope 43.6 km² | overall design scope approx. 11.41 km² | three key areas 369.3 ha

Overall Design Area - Site Overview Plan

Boundary, land use, green space and the three Key Areas are projected from this package's geometry/ layers; the boundary is the organiser's provisional rough extent, not a red line.



Design area: approx. 11.41 km² (provisional design model; recomputed when the official boundary is issued)


site-overview

Figure 01: Overall spatial structure (one spine, three terraces, two wings)

- Historical motif: the self-reliance of Zhan Tianyou's 1909 人-shaped switchback, translated into contemporary AI self-reliance.
- 4 pilgrimage landmarks: Renzi Terrace (1909), Gaokao Gate (1949), Clock of Compute (1980), Origin Stele (2026).
- 2 wings: Zhongguancun Tech Service Wing (west) and Xiaoyuehe Scenario Innovation Wing (east).

Land-Use Structure Plan (block level)

31 parcels coloured by land-use code; legend and area statistics recomputed from land_use.geojson.



Land-use area statistics (recomputed from land_use.geojson)

Code	Land-use category	Area (ha)	Share
1401	Park and green space	257.1	22.5%
05	Commercial and business services	169.7	14.9%
0701	Urban residential	147.0	12.9%
0802	Research and development	138.7	12.2%
0803	Cultural	81.8	7.2%
0804	Education	73.1	6.4%
1402	Buffer green	55.1	4.8%

Code	Land-use category	Area (ha)	Share
1403	Civic plaza	49.4	4.3%
08	Public administration and services	45.7	4.0%
16	Reserved land	36.5	3.2%
0702	Community service facilities	35.9	3.1%
0806	Health care	26.4	2.3%
0805	Sports	25.0	2.2%

Total 1141.3 ha (31 parcels)

land-use-structure

Figure 02: Land-use structure and anchor catchment partition

- Complete partition: 4 smart stations (TOD) and 14 innovation anchor catchments seamlessly partition approx. 11.41 km².
- Functional balance: R&D innovation labs, educational synergy, talent housing and continuous blue-green parks.
- Strict integrity: no gaps, no overlaps; recomputed against the geometry layers in EPSG:4548.
- 31 parcels total 1,141.3 ha, from the same source as metrics.json site_area_sqm.


JINGZHANG RISING Detailed Design of the Three Key Areas

BOARD 02 / 03 · Origin Terrace 193 ha | Origin Works 104 ha | Bell Hub 72 ha
15 blocks with concept ranges | FAR and height guidelines | Report Card Kiosk deployment

Enlarged Plans of the Three Key Areas

Block outlines are parcel boundaries; public space, primary streets and Report Card Kiosk positions are located on the plan (positions indicative).


智源台 Origin Terrace



Area 192.92 ha




原点坊 Origin Works



Area 104.32 ha



智汇钟 Bell Hub



Area 72.05 ha




Block outline (parcel) Public space node Primary street Report Card Kiosk

Block outlines are labelled with their land-use code; kiosk positions follow the deployment table in proposal.md.

key-areas


Key-area plan (diagrammatic, not a redline)

Recomputed: 192.92 ha | slow mobility 5,791 m | density 30.0 m/ha | green ratio 29.9%



Block (with coverage cap) Slow-mobility spine Public space node Report Card Kiosk Water

Full-stack walking axis section (ZZ-A to ZZ-B)



Pedestrian-first, no through carriageway; service vehicles ≤20 km/h, canopy ≥70%.
Boundaries are the organiser's provisional rough extents: concept only, not a redline or precise-area basis.


key-areas-zhongzhiyuan

Origin Terrace / Zhongzhiyuan (193 ha)

- Blocks: ZZ-A frontier lab, ZZ-B incubation, ZZ-C talent housing, ZZ-D service, ZZ-E green space.
- Concept guidelines: FAR 1.6–3.5, height 24–60 m, building coverage ≤ 35%.
- Public anchor: Renzi Terrace memorial, Qinghe smart station TOD and the RCK-01 kiosk.
- Mobility: slow-mobility density 30.0 m/ha, length 5,791 m.


Key-area plan (diagrammatic, not a redline)

Recomputed: 104.32 ha | slow mobility 3,092 m | density 29.6 m/ha | public space 34.4%



Block (with coverage cap) Slow-mobility spine Public space node Report Card Kiosk

Origin Works pedestrian spine section (YD-A to YD-E)




Closed to private vehicles; coloured permeable concrete cycle lanes; kiosk in the central garden.

key-areas-origin-works


Key-area plan (diagrammatic, not a redline)

Recomputed: 72.05 ha | slow mobility 2,283 m | density 31.7 m/ha | green ratio 30.2%



Block (with coverage cap) Public space node Report Card Kiosk Heritage buffer setback ≥12 m

AI-native retail street section (DZ-C)



Transit plus slow mobility, private vehicles excluded; demountable spill-out zones.

key-areas-dazhongsi

Origin Works (104 ha) and Bell Hub (72 ha)


- Origin Works blocks: YD-A open source hall, YD-B campus link, YD-C apartments, YD-D mixed TOD, YD-E origin plaza.
- Origin Works guidelines: FAR 1.2–2.8, height 18–45 m, coverage ≤ 35%; slow-mobility density 29.6 m/ha, length 3,092 m.
- Bell Hub blocks: DZ-A green compute, DZ-B industry engine, DZ-C commercial, DZ-D living, DZ-E quadrant park.
- Bell Hub guidelines: FAR 1.8–3.6, height 24–60 m, coverage ≤ 35%; slow-mobility density 31.7 m/ha, length 2,283 m.
- Public anchors: Gaokao Gate at Tsinghuayuan station, Wudaokou TOD, Clock of Compute, the Dazhongsi four-quadrant concourse, RCK-02 and RCK-03 kiosks.

The design scope and the three key areas use the organiser's provisional rough substitute boundary: concept recommendations only, never a statutory redline, an approval basis or a precise-area basis. Once official polygons are published the geometry, metrics, drawings and HTML must all be recomputed.

Submission package: cf3901646 | Author: Charlie JIANG | Licence: COMMUNITY-DISPLAY-ONLY

Slow Mobility, Blue-Green and Water Overlay Plan

Cycling network, pedestrian priority, green corridors and waterfront are overlaid on one base plan; each layer is listed in the legend below.



0 500 1000 1500 2000 m


- Principal greenway (slow-mobility spine)
- Commuter cycleway
- East-west stitch pedestrian link
- Smart-station connector
- Secondary street
- Station forecourt public space
- Heritage park spine greenway
- Park and green space
- Buffer green
- Stitch green link
- Waterfront edge (Qinghe; no separate water layer in package)
- Pedestrian priority zone (within Key Areas)

Slow-mobility network 25,932 m (greenway + stitch links + cycleway, recomputed from roads.geojson)

mobility-bluegreen

Slow-mobility network and station-area feeders (by key area)

Lengths and densities are recomputed from geometry;; sections and timings are concept proposals




mobility-strategy

Figure 04: Mobility and blue-green public space system

- North-south spine: 9.0 km continuous greenway plus a commuter bike express lane.
- East-west stitch: 7 pedestrian stitch corridors overcoming the former railway severance.
- Station integration: 4 smart stations with 500 m covered walkways, bike hubs within 50 m and EV charging ≥ 40%.
- Intersections and parking: 12 cm raised crossing tables, 1:12 ramps and parking caps by key area.

Report Card Kiosk: elevations and footprint (front / side / clear zone)

Overall 1,800 x 2,200 x 2,800 mm | footprint 3.96 m² | freestanding, demountable



Active mode shows the six answer-sheet items and human-takeover records; the plate and QR code stay readable when unpowered.

Deployment: RCK-01 Origin Terrace | RCK-02 Origin Works | RCK-03 Bell Hub | RCK-04 spine stitching link #3


report-card-kiosk

Figure 05: Recomputed metrics and evidence chain

- 33 core metrics: 30 known metrics recomputed deterministically; 3 statutory controls kept strictly 'unknown'.
- Report Card Kiosks (RCK): footprint 3.96 m², 1,800 × 2,200 × 2,800 mm, dual-mode operation with a physical fallback.
- Gate validation: all 4 verification gates and 30 universal property invariants 100% passed.
- Traffic-light governance: green for full access, yellow for 7-day rectification, red for immediate shutdown and a switch back to human service.

Metrics evidence: equal-area square diagrams of the three key areas

Each square is drawn with the side length of the key area's actual area; areas, lengths and ratios are recomputed from the geometry/ layers



Basis: slow mobility = greenway + walking links + cycle lanes; ratios are layer-to-key-area intersections. Boundaries are provisional rough extents.

metrics-evidence