

THE LEVELING LINE

JING-ZHANG AI INNOVATION BELT


Method and identity: governance by closure error, and the visual system

THE LEVELING LINE

THE LEVELING LINE

A city that publishes its own error.

A city that publishes its own error.




Leveling is not about measuring accurately. It is about measuring back.

Depart from the origin, carry the height station by station, run the circuit and return — the part that does not land back on the datum is the closure error.

Within tolerance every station is accepted; over tolerance the whole run is void and re-measured, and no single station may be patched.

This proposal applies that hundred-year-old rule where a wrong reading injures someone: low-speed robots and AI public services.

IDENTITY: MARK, CONSTRUCTION AND APPLICATIONS



THE LEVELING LINE

THE LEVELING LINE

The mark draws the method, not decoration: the datum line departs the origin, rises, returns, and does not quite land back on the datum — that red height difference is the closure error.

CONSTRUCTION

CONSTRUCTION



- **Origin benchmark** Ring and crosshair; the network's starting point
- **Datum line** Dashed is the ideal datum; solid is the measured route
- **Rise and return** One complete out-and-back transfer
- **Red; the height difference** f: what does not land back

Anyone using this mark declares that their conclusion can be independently re-measured.
The mark does not grant trust; it declares that the claim can be re-measured.

VARIANTS


VARIANTS



Two-colour · primary



Single-colour · etched and cast



Reversed · dark ground




Minimal · below 16px

The minimal variant drops the ideal-datum dashes and keeps only the route and the red height difference; below 16px it still reads as “a line that did not return” .


APPLICATIONS

APPLICATIONS


Benchmark plaque



Reading board · L2 closure stele



Data interface icon



Extension rule

Numbers are unique and ordered by merge time, implying no relative merit.

Five standard parts: stone and plaque, reading board, dwellable seating, step-free guidance and complaint entry, at common specifications with open drawings.

No unlicensed typefaces, images, trademarks or portraits are used.

The mark is a directional proposal and geometric construction for a professional team to develop; it is not a finished identity. All graphics are generated from geometric parameters and contain no unlicensed typeface, image, trademark or portrait. The 0.26 shown on the reading board is illustrative, not a measured result.

REGIONAL COORDINATION INTERFACES: EXTENDING THE LEVELLING NETWORK

FIG.11
Regional coordination interfaces: extending the levelling network

An executable form of coordination: how two levelling networks join

AN EXECUTABLE FORM OF COORDINATION: HOW TWO LEVELLING NETWORKS JOIN



A joint observation produces a number, not an intention:

Each network reads the same public question set; the difference is the cross-network closure error. Within a jointly agreed tolerance, the two networks' records may be mutually recognised; over it, each re-surveys, and no declaration of partnership substitutes for a reading.

Nobody gives up authority: a joint observation asks only that conventions be comparable, not that organisations merge.

What each of the five partners exchanges, and what it does not


Partner	Stage	Exchanges	Explicitly does not exchange	Precondition for the interface
BDA (Yizhuang)	Volume production and high-level AV road testing	Mutual recognition of closure records across complementary speed domains	Not one admission: an F1 pass here admits a device to pedestrian density, not to a carriageway, and the reverse also holds	Both parties confirm the speed-domain split and test protocols
Future Science City	Corporate research institutes and engineering	Scenario demand and real user density	No claim on IP; no scheduling on anyone's behalf	Wing benchmarks built and a first baseline taken
Huairou Science City	Large facilities and basic research	The measurement method itself: how f is defined, cycle length, the statistics behind revising F	No scenario data is exchanged; the coordination is methodological, not applied	The closure convention published and open to methodological review
Beiwei Community	The innovation community the taskbook names	Reciprocal joint points; exchanged review parties	This proposal does not know its positioning and does not set its benchmark order	Each party names at least one publicly reachable joint point
Beijing-Tianjin-Hebei	Cross-provincial coordination	Cross-provincial recognition of the tolerance convention	No direct recognition of records; without a shared convention they are not comparable	Tolerance definition and revision procedure agreed across provinces

None of the five rows has been confirmed by the party named.
No internal plans are known, nobody is committed, no agreement is assumed; each row is an interface to evaluate independently.

Each partner's stage is described from publicly available general positioning and is unconfirmed by them. The speed-domain relationship in the first row must be settled against both parties' actual test protocols. This sheet proposes interfaces; it commits nobody and is no government determination.
THE LEVELING LINE · jiangmuran · Concept advice on provisional boundaries; not a substitute for statutory planning
Recomputed in EPSG:4548 · exchanged in EPSG:4326

KEY AREAS AND BENCHMARK LAYOUT

FIG.04
Three key areas and benchmark layout



Benchmark orders

BENCHMARK ORDERS

- Origin benchmark: Annual origin and closure check
- First-order benchmark: Annual re-survey
- Second-order benchmark: Quarterly re-survey
- Third-order benchmark: Monthly re-survey

Closure verdict

CLOSURE RULE

A scenario departs BM-0, is read at each station along a connecting route by a different party, and terminates at a first-order point; the computation closes at BM-0.

- $f \leq F$ level for this cycle: it may operate and enter the next cycle
- $f > F$ the whole route returns for re-survey and drops to the non-AI equivalent

Amending only the worst station is not allowed. Tolerance F may tighten on evidence; it may never loosen because a scenario failed.

Layers: geometry/key_areas.geojson, roads.geojson, public_space.geojson, green_space.geojson. Drawn directly from the submitted geometry by the accompanying scripts and recomputable (scripts in the accompanying issue). The line is rotated horizontal per alignment-sheet convention: south (Xizhimen) left, north (Qinghe) right.

THE LEVELING LINE · jiangmuran · Concept advice on provisional boundaries; not a substitute for statutory planning

THREE KEY AREAS AND THEIR SURVEY ROLES

KEY AREAS AND SURVEY ROLES

- Dazhongsi AI Industry Cluster: BM-2 first-order benchmark, high-frequency reading point | AI-native consumption and business
- Beijing AI Origin Community: BM-0 origin benchmark, network origin and closure computation | public evidence hall and stone L1
- Zhongzhiyuan AI Acceleration Area: BM-1 first-order benchmark, tolerance datum | where F is set

Key-area boundaries are provisional substitutes: official polygons are unpublished. Shown dashed; not usable as a redline or as a precise-area basis.

Recomputed in EPSG:4548 · exchanged in EPSG:4326

THE LEVELING LINE


JING-ZHANG AI INNOVATION BELT

Routes and the street: walking, blue-green, and eye level

SLOW MOBILITY, BLUE-GREEN AND CONNECTING ROUTES

FIG.05

Slow mobility, blue-green and closing routes



East-west stitching points (11)

EAST-WEST STITCHING POINTS

The class rests on one measurable fact: whether OSM already maps a crossing within 60 m of the intersection. If it does, Class A. If it does not, the need is registered and left ungraded — separating Class B (channelisation) from Class C (new structure) is a traffic study's conclusion, not this proposal's.

Yinquan Rd	Class A	10 m	Xueyuan South Rd	Class A	25 m	N 4th Ring Rd Middle	Class A	30 m	N 3rd Ring Rd	Class A	33 m
Beitucheng West Rd	need registered only	65 m	Xizhimen North St	need registered only	68 m	Tsinghua East Rd	need registered only	86 m	Shibanfang South Rd	need registered only	146 m
G6 service road	need registered only	166 m	G6 service road	need registered only	175 m	Zhixin Rd	need registered only	201 m			

Distances are to the nearest mapped crossing. OSM is crowd-sourced: "need registered only" means OSM shows none, not that none exists on the ground.

The two connecting routes

CONNECTING ROUTES

- North connecting route RT-N**
BM-0 → BM-303 → BM-22 → BM-1 (terminates at a first-order point; the computation closes at BM-0)
- South connecting route RT-S**
BM-0 → BM-302 → BM-21 → BM-301 → BM-2 (terminates at a first-order point; the computation closes at BM-0)

Each station is read independently by a different review party: professional body, operator, resident representatives and international visitors — none may be omitted.
Homogeneous review parties would bias the closure error systematically low and drain it of meaning — a risk this mechanism declares.

SLOW MOBILITY AND THE BLUE-GREEN NETWORK

SLOW MOBILITY AND BLUE-GREEN

Spine	A continuous walkable public axis; walking and cycling take priority	9,443 m
Green corridor	Buffered both sides of the spine, forming a continuous blue-green interface	120 m each side
Station-point unification	courses double as third-order benchmarks, so re-survey happens where footfall is densest	3
Universal first	Step-free access, lighting, drainage and shade come before any smart facility	Precondition

A street with sensors that a wheelchair cannot enter
is not eligible for re-survey.

Tolerance classes

TOLERANCE CLASSES

F1	strictest	daily safety or administrative acts	S04 · S06 · S10 · S11
F2	Medium	individual rights	S02 · S03 · S05 · S09 · S12
F3	width	Information only	S01 · S07 · S08

Layers: geometry/roads.geojson, green_space.geojson, public_space.geojson. Drawn directly from the submitted geometry by the accompanying scripts and recomputable (scripts in the accompanying issue). Routes are concept advice and do not constitute engineering alignment.

THE LEVELING LINE · jiangmuran · Concept advice on provisional boundaries; not a substitute for statutory planning

Recomputed in EPSG:4548 · exchanged in EPSG:4326


THE BENCHMARK ON THE STREET AND HOW THE KERB IS SHARED

FIG.10

The benchmark on the street, and how the kerb is shared

What a benchmark looks like at eye level

A BENCHMARK AT EYE LEVEL · third-order BM-301 · elevation 1 m = 138 units



Two of the five standard components are hard constraints: seating must have armrests, and the complaint entry must offer a non-scan method. A rule you cannot see in the drawing is a rule the drawing does not contain.

Kerb allocation in priority order

KERB ALLOCATION IN PRIORITY ORDER · sequence and precedence only, no widths

1 Emergency access and fire	2 Step-free boarding, turning	3 Walking and dwelling	4 Public transport and cycle parking	5 Device charging and standby	6 Kerbside car parking
Never occupied	Not occupied	Never squeezed below the level-of-service reserve		Sited only from what remains after the car above	

satisfied first →

→ allocated last

The order is itself a position: device charging sits behind pedestrians and accessibility, which means introducing devices must not be paid for with degraded walking conditions. Winter snow storage must be reserved at this stage alongside the device and pedestrian lanes — piled on the device lane the devices stop; piled on the pedestrian lane people are pushed toward the carriageway, which is worse.

The elevation is drawn at 1 m = 138 units. The figures are a scale reference and a statement about who is present, not a rendering. The section expresses sequence and precedence only and carries no widths — capacity must be computed on site from measured clear width, and a figure not derived from measurement is fabricated certainty. Component specifications are in geometry/public_space.geojson and the scenario cards; positions await official boundaries and title verification.


THE LEVELING LINE · jiangmuran · Concept advice on provisional boundaries; not a substitute for statutory planning

Recomputed in EPSG:4548 · exchanged in EPSG:4326

EVIDENCE CHAIN AS AN UNCLOSED LEVELING CIRCUIT

FIG.02

Evidence chain and submission package: a leveling circuit not yet closed



Act One: measuring this open call itself

MEASURING THE OPEN CALL ITSELF · as of 2026-08-09 · 354 merged · 354/354 fetched · PR numbers past 1000

354

Merged proposals (git tree, authoritative)

The gallery index lists 309 at the same moment — 45 behind

29.9%

Machine-readable disclosure field empty

106 of 354 still hold the scaffold placeholder or are empty

113 → 8

Distinct strings written → actual model families

The GPT/Codex family alone is written 53 ways across 156 proposals

The “machine-readable” disclosure field is not machine-readable.

charter.6 requires disclosing the generation method and charter.5 requires it structured and agent-readable, yet none of the four gates checks this field. Nobody can aggregate “which models produced this call” from it.

The fix is light: split “model” into an enumerated family plus free-text detail, and add one enumeration check.

This proposal is the instrument for the missing last step: compute the closure error, and give it consequences.

Registers answer “what did the system declare” and assessments answer “what do experts think” ; closure error answers “how much does the conclusion differ across nodes and across time for the same public question” .

Sources: visual/assets/census.json, field_map.json and the first-round (184-file) snapshot agent_declarations.json, all shipped with the package. The authoritative source is the GitHub git tree, not the gallery index, which lags. Generation scripts are in the accompanying issue and are re-runnable. The corpus grows daily; recompute before citing.

THE LEVELING LINE · jiangmuran · Concept advice on provisional boundaries; not a substitute for statutory planning

Recomputed in EPSG:4548 · exchanged in EPSG:4326

RECOMPUTED METRICS AND MEASURED EVIDENCE

FIG.06

Recomputed metrics and closure-error evidence

METRICS RECOMPUTATION

RECOMPUTED METRICS · EPSG:4548

Class 1, measured: recomputable directly from this package's geometry

Overall design area	11,412,825	m ²
Spine length	9,443	m
Benchmark count	8	
Green corridor ratio	0.1966	
Public measurement-point ratio	0.0642	
Indicative footprint area	82,276	m ²
Key areas	3	
Green ratio (land-use partition basis)	0.1220	
Phase increments, summed	2,920,311	m ²

A further 26 count metrics (unit: count) ship in metrics.json: scenario cards, personas, landmarks, case studies, renewal projects, phases, land-use classes, errata entries, rights-ledger entries and more — each recomputed by the build from a shipped artefact and not listed in this table.

Class 2: requires official regulatory support; held at unknown

Floor area ratio · building height · density · setbacks · road redlines

Filling estimates into a gap while official data is absent is fabricated certainty.

Class 3: requires continuous re-survey calibration; no baseline yet

Per-scenario closure error f · tolerance compliance rate · non-AI path coverage · resident-initiated re-surveys

Baselines follow one near-term cycle. This proposal says no data exists rather than passing intent off as measurement.

Every class-1 value is computed from the submitted layers by the accompanying script.
A number nobody can recompute is not evidence — and that standard applies to this proposal first.

Track coverage: the two thinnest tracks are the two highest-risk ones

TRACK COVERAGE · tracks are multi-select, so shares sum above 100%




Robotics and autonomous mobility 18, AI public services 32 — not unimportant, but hard to write: taken seriously they force safety, licensing, privacy, accessibility and appeal into the open, and cannot stop at the concept layer.

MEASURED CORPUS

MEASURED CORPUS · n=354 (git tree) · index lists 309, 45 behind · 2026-08-09


Structural convergence

Proposals sharing the same structural motif, independently generated



Meta-symbol saturation

Proposals building their identity on the same source image



Surveying / leveling ← this proposal 2


Block / token 0

Vein 95 and proof/verification 100 are heavily saturated; surveying/leveling 2.
Leveling is not another railway-operations metaphor. It is a method for how trust is established.

Sources: this package's metrics.json and visual/assets/field_map.json, both shipped with it; the authoritative source is the GitHub git tree. The independent verifier visual/assets/verify.js checks every class-1 metric. Generation scripts are in the accompanying issue. The corpus grows daily; re-run before citing.

THE LEVELING LINE · jiangmuran · Concept advice on provisional boundaries; not a substitute for statutory planning

Recomputed in EPSG:4548 · exchanged in EPSG:4326



THE LEVELING LINE

JING-ZHANG AI INNOVATION BELT

The kit of parts, and the overall concept

LANDMARKS, KIT OF PARTS, SIGNAGE SYNTAX AND OPERATING CYCLE

FIG.09

Landmarks, kit of parts, signage syntax and operating cycle

Three AI pilgrimage landmarks

THREE LANDMARKS · spoken in engineering language; no spectacle

L1 The origin benchmark stone


BM-0 · AI Origin Community



Every merged proposal's number is set into the paving — contributors' GitHub IDs are inscribed here. It is not grand. It is accurate, and must be accurate enough to be reused a century later.

L2 The closure stele

BM-1 · Zhongzhiyuan



A public reading wall, updated live, showing each scenario's closure error against its tolerance. Exceedances are marked in datum red. The value of this landmark is that it is allowed to look bad.

L3 The zeroing point


BM-2 · Dazhongsi



An annual civic ceremony space: the line's readings are zeroed here, tolerance revisions are read out, and scenarios returned for re-survey in the past year have their disposition explained. On ordinary days it is a public dwelling space.


Kit of parts for public space: five standard components

KIT OF PARTS · common specifications and open drawings, so any new node joins in one language




1 Stone and plaque

The number is the position, the order and the cycle Visible on site; no internet needed




2 Reading board

Visible on site; no internet needed



3 Dwellable seating


With armrests: older people rely on them to stand



Clear width and gradient enter the re-survey items

4 Step-free guidance

Read by the users themselves



5 Complaint entry

A non-scan method is mandatory, or the right does not exist for P4

Signage numbering syntax (agent.5)

A visitor reading the number knows which order they are standing at and how often it is re-measured

BM-0	Origin benchmark	Annual origin and closure computation
BM-1 / BM-2	First-order benchmark	Annual re-survey
BM-2x	Second-order benchmark	Quarterly re-survey
BM-3xx	Third-order benchmark	Monthly re-survey
RT-N / RT-S	Closing route	Semi-annual re-survey of the whole line

Operations are organised by re-survey cycle, not by festival calendar (agent.6)

Events are therefore governance actions, not publicity

Monthly	Community day	Third-order BM-301/302/303	Led by P4 older residents, P5 wheelchair users, P7 frontline workers
Quarterly	Scenario open day	Second-order BM-21/22	Led by P2 developers and P3 students and faculty
Semi-annual	Route re-survey	Closing routes RT-N / RT-S	Led by professional bodies, with all four review categories present
Annual	Zeroing ceremony	3 The zeroing point	Readings zeroed, tolerance revisions read out, returned scenarios accounted for


Developer conversion path: take part in re-survey → propose a scenario → enter the test field → obtain closure clearance → operate
International communication uses published readings as its material, never commitments.

The $f=0.26$ / $f=0.14$ on the reading boards are illustrative, not measured results. f is always a deviation: larger is worse, and $f \leq F$ is the passing test. Landmark siting requires heritage and engineering review; this proposal does not pre-empt it. The components are a directional proposal for a professional team to develop and are not construction drawings.
THE LEVELING LINE · jiangmuran · Concept advice on provisional boundaries; not a substitute for statutory planning
Recomputed in EPSG:4548 · exchanged in EPSG:4326

OVERALL CONCEPT AND SITE CROSS-CHECK

FIG.01

Overall concept and site cross-check: spine, core nodes, inferred boundaries, surveyed park



Legend and how to read it

LEGEND · surveyed data and inferred boundaries are shown separately

Surveyed (independently checkable)

- Jing-Zhang Railway Heritage Park (OSM survey, 17.49 ha)
- Disused railway (14 segments, 3,028 m)

Inferred (not usable as a redline)

- Coordinated research area 43.6 km²
- Overall design area 11.4 km²

This proposal's design (generated against inferred boundaries)

Blank-block edges follow the existing arterials; they are not a parcel subdivision or an ownership boundary

- Cultural use (0803)
- AI R&D and research (0802)
- Community services and support (0702)
- Industry and commercial services (05)
- Park and green space (1401)
- Urban road land (1207)
- Left blank by this proposal (code 16)
- Spine (design centreline)
- Tiered benchmarks

The line to read on this sheet is the red one.
Research area and surveyed park agree 100%, so the announced bounds do not conflict with actual geography; the discrepancy is confined to the overall design area.
This proposal's spine is displaced with it. Marked here rather than hidden.

Two independent routes to the same object

TWO INDEPENDENT ROUTES TO THE SAME OBJECT



The same instrument also measured this proposal:
the submitted spine lies 1116.7 m from the surveyed park, because it was generated against the provisional boundary.
A recomputability standard invoked only when it flatters the author is not a standard.

Surveyed data © OpenStreetMap contributors · ODbL 1.0 · Overpass API 2026-08-08. Script and conventions in visual/assets/osm_reference.json; re-runnable. OSM is crowd-sourced and the park polygon may cover only the mapped section; the provisional boundary is itself inferred. This sheet reports the difference and does not adjudicate which is right.
THE LEVELING LINE · jiangmuran · Concept advice on provisional boundaries; not a substitute for statutory planning
Recomputed in EPSG:4548 · exchanged in EPSG:4326